



An 18c. 5 bay barn, possibly axled on one side with a corresponding lean-to with cat-slide roof on the other. The roof is hipped and tiled, the walls weatherboarded on an ironstone plinth.

Apparently all one build, but with some re-used timbers. Roof originally had clasped purlins, Queen posts and collars. Posts & braces have chiselled carpenter's marks, tie beams have scratched carpenter's marks. Braces straight, as are short down braces in walls. All joints pegged. Roof new with ridge board. The "aisle" appears to be original, with its own rafters and large straight braces up to wall plate. One post has 1783 roughly carved on it. Two South bays floored over.

Porch weatherboarded on brick plinth. "Lean-to" has ironstone plinth. Many alterations to barn.

